

IGHEM - Montreal 96

" The Efficiency Measurement at Kalan Power Plant: Results and ideas "

Kiani Abdulsamad

Head of Electrical & Mechanical Dept.

Iran water & Power Resources Development CO.

P.O. Box 13185 - 579 Tehran-IRAN

Tel: (+98) 21-8839730

Fax: (+98) 21-8839729

Résumé

Comme Le rendement des turbines dans les stations hydro-électriques est l'un des plus importants " valeurs de garantie " , La méthode de mesure et de calcul des quantités correspondantes devront donc être prise en considération d' une manière très attentive.

Cet article est essentiellement consacré aux essais de mesure du rendement des turbines dans la station hydro-électrique de KALAN et à la comparaison des résultats avec des " valeurs de garantie".

D' ailleurs, quelques recommandations concernant l' augmentation de la précision des mesures et du calcul du rendement réel des hydro-turbines seront présentées.

Summary

As the efficiency of the turbines in hydro electric power plants is one of the most important guarantee value, then the measuring method of the relevant quantities and calculations should be considered quite well.

This paper will mainly deal with the tests of measuring the turbines efficiency of the kalan hydro power plant and comparison of the tests results with the guarantee values.

Also, some recommendations towards increasing the accuracy of the measurements and calculation of the actual efficiency of the hydro turbine are presented.

1. Introduction

The kalan hydroelectric plant is owned and operated by Tehran regional water board (TRWB) . The owner awarded the contract for the electromechanical equipment of kalan power plant (3*38.5 MW) to the GIE co., Italy.

The studies of the plant was done originally by Sir Alexander Gibb & partner, England and the supervision of the works and commissioning was done by Lar Consulting Engineers, Iran.

The project was completed in late 1988, and since that time the units are in operation according to the reservoir level and requirements of the network .

During 7 years of operation, the O & M staff of the plant haven't reported any serious problems.

The delayed efficiency tests of the units was done in 1992 by a specialized team from the Riva Hydroart s.p.a., Italy.

2. Description of kalan power plant

The kalan hydro plant is approximately 30 km northeast of Tehran, the capital of Iran. Its purpose is to divert a part of the impounded water of Lar earthfil dam into the existing Lalyian reservoir, in order to augment the supply of drinking water to Tehran as the demand increases.

A low pressure tunnel (approximately 19.9 km long) connects the Lar reservoir to a surge chamber from which a high pressure tunnel and penstock (approximately 1600 m long) leads to a distributing manifold, which supplies three hydro - electric generating sets (each 38.5 MW) and bypass valve(The layout is shown on figure No.1-1). Hydraulic conditions preclude the operation of more than two units at any one time and the additional unit is intended for standby purposes only in order to assure security of water supply to Tehran .

The units are capable of operating as synchronous condensers.

The three turbines are equipped with pressure relief valves, preventing excessive pressure rise during load rejections .

A spherical valve of 900 mm diameter is located at the ahead of each turbine.

Each vertical shaft Francis turbine is rated at 39.49 MW at 750 rpm with nominal discharge of $9.25 \text{ m}^3/\text{s}$ at a net head of 470.5 m.

The generators are vertical shaft, direct coupled (via an intermediate shaft) to the turbine, salient pole, synchronous type, generating (each) 38.5 MW at 50 HZ, 13.8 KV and power factor of 0.85.

The units are intended to operate as peaking units , but could operate continuously for prolonged periods at maximum output and discharge.

The average annual generation of the plant is 200 Gwh.

The output of each generator is transmitted through a 45 MVA three - phase transformer to the 230 KV switchgear station for interconnection with the national network.

3. Measuring Systems

3.1. Discharge measurement

According to the contract, the discharge was measured by means of currentmeters in the penstock having a 2.1 m diameter. In compliance with the IEC codes 41-1963, 13 currentmeters (SIAP currentmeters) with diameter of 120 mm were used. The current meters were located on a rectilinear portion of the penstock.

The currentmeters were calibrated at the calibration laboratory of the waters federal service of Bern and were provided with the relevant calibration certificates.

The arrangement of the currentmeters and relevant information are indicated on the figure No.1-2

3.2. Head measurement

In compliance with the IEC codes 41- 1963, measurement of upstream pressure was done by means of a dead weight manometer (Neyrpic accuracy manometer) connected to the pressure taps at the inlet of spiral casing (four taps, which enables to measure the pressure mean value) and measurement of downstream level was done by means of a graduated bar. Before and after the tests, The dead weight manometer was statically calibrated according to the above mentioned IEC codes.

3.3. Differential pressure measurement

The differential pressure on winter kennedy taps was measured by means of a differential mercury manometer, utilizing the taps provided on the sprial case.

Arrangement of the measuring systems described at para. 3.2 and 3.3 are indicated on the figure No.2

3.4. Measurement of the electric power

The electric power at the terminals of generator was measured by means of three wattmeters with precision class of 0.2.

Also three ammeters with precision class of 0.5 and one voltmeter with precision class of 0.5 were used. The mentioned instruments were connected according to IEC codes 41-1963 for generator with grounded neutral.

All the utilized instruments were provided with the relevant calibration certificates.

4. **Test procedure**

In order to check the results of the tests against contractual guarantees, the tests was performed on each unit separately (only one in operation) and then on two units (each of two units in operation).

4.1. One unit in operation

The tests were performed at net heads between reference heads of 470.5m (gross head of 485.5 m) and 449 m (gross head of 464 m) as indicated in the contract.

On the hill diagram of figure No. 3 the relevant reference points are shown as C and B.

The measured values were subsequently converted to the reference net heads with the guarantees, as stated in the IEC codes 41-1963. Besides of the guarantee discharge of $9.25 \text{ m}^3/\text{s}$, the tests was performed at various decreased discharges.

The above mentioned tests were alternately extended to two units by the measuring systems as already indicated.

4.2. Two units in operation

The tests were performed with two units in operation and a total discharge of $18.5 \text{ m}^3/\text{s}$ was flowing through the penstock.

As the net head of the tests was differ from the net indicated in the contract (404.04 m), the measured values were converted to the reference net head with the guarantee as stated in the IEC codes 41-1963 on the hill diagram of figure No. 3, the relevant reference point is shown as point A.

5. Results Processing

5.1. Discharge calculation

The signals at the outlet of each currentmeter (1 pulse every $1/2$ turn) were routed by cables to a multichannel pulse counter (visualized on LCD) At the same time the signals were stored by a computer and processed for discharge calculation in real time.

The number of turns of each currentmeter, duration of the test and processings for calculation of the water velocity for each currentmeter was tabulated by a printer.

Finally, in compliance with the IEC codes 41-1963 for the procedures of graphic integration of $\int v dr^2$ and $2 \int v r dr$, the relevant graphs were recorded by a plotter (HP) , piloted by a computer.

5.2. Head calculation

The head was calculated by the formulas specified in the IEC codes 41-1963 (chapters II and IX).

5.3. Turbine input(Pd)

The turbine input was calculated by the formula indicated in IEC codes 41-1963.

5.4. Turbine output(Pt)

The turbine output was determined by the following formula:

$$Pt = Pr + Pa$$

Pr: Active power measured at the terminals of generator

by the instruments mentioned at para.3, with the due correction of the errors attributable to the instruments and relevant instrument transformers.

Pa: Mechanical and electrical losses measured during generator efficiency tests by means of calorimetric tests.

According to the contract, the generator losses includes the thrust bearing losses attributable to the turbine.

5.5. Efficiency calculation

- One unit in operation

The turbine efficiency was calculated as ratio of the turbine output (Pt) to the turbine input (Pd).

- Two units in operation

The output of each turbine (Pt1, Pt2) was measured by means of relevant set of instruments.

on the basis of the above mentioned measurements, the mean efficiency of the two turbines was determined by the following formula:

$$\eta_m = \frac{Pt_1 + Pt_2 \cdot 102}{H_1 + H_2 \cdot \gamma \cdot 1000 \cdot \frac{Q}{2}}$$

5.6. Calculation of winter kennedy taps constant

The constant of the winter kennedy taps was determined as the ratio of the discharge (measured by the currentmeters at various load) to the root of the differential pressure (measured by the differential manometer) at the same load, thus given by the following formula:

$$K = \frac{Q}{\sqrt{\Delta h}}$$

Q : discharge in m³/s

Δ h : differential pressure mm Hg^{1/2}

on the figures No.4-1 to 4-13 samples of calculations and tests relevant to para. 5.1 to 5.6 and also other information for the specific condition are shown.

6. Comparison of the tests results against contractual guarantees.

The samples of the tests results (calculations and curves) for one unit and two units in operation are indicated on figures No.4-1 to 4-13 .in compliance with the IEC codes 41-1963 (chap V.II) the tabulation of the measurements and test results are indicated on figures No.5-1 to 5-2 for one unit (unit No.1) and two units (units No.1 and No.2) in operation.

According to the contract, " the efficiencies of the model turbine, full size turbine , generator and the complete generating set shall not be less than the values stated below for operation at normal speed, rated voltage and rated power factor overexcited, under the mean gross head of 464 m, the turbine discharging $9.25 \text{ m}^3/\text{s}$ ".

Item	No. of operating set	
	1	2
output (MW)	36.75	33
Discharge (m^3/s)	9.25	9.25
Net head (m)	449	404.04
Model turbine efficiency(%)	90.33	90.29
Full size turbine efficiency (%)	* 92.08(92.10)	* 92.04 (92.16)
Generator efficiency(%)	97.48	97.32
Efficiency of complete set (%)	89.76	89.57

* Obtained from the turbine efficiency tests results.

As the model was made at a scale of 1/4 and the scaled - up efficiency calculated from the model peak efficiency by the moody formula (IEC 193 for Francis turbine):

$$\frac{1-\eta_p}{1-\eta_m} = (1/4)^{0.2}$$

giving $\eta_p = \eta_m + 2.3$ percent

And with regard to the test results, which shows comparatively higher peak efficiency on the prototype turbine, Finally it was confirmed that the mentioned guarantees (relevant to the turbines) has been fulfilled.

7. Ideas

The efficiency of the turbine is dependant on its hydraulic design as well as its present condition.

In addition to the turbine design, the actual efficiency loss is caused by several factors.

A number of these factors and also recommendations are presented as follows:

- 7.1. For field testing of hydro turbines, using of modern technology (computrized) should be noticed quite well.

Modern technology provides real time recording of measured data, immediate control and evaluation of the measurement, high accuracy and reduced error frequency of the measurements. Good post - processing of the data is also necessary to achieve a clear presentation of the results.

Of course, proven software and qualified test personnel are needed for successful measurement.

- 7.2. If the tests are done after a long period of operation of the units, then some matters should be noticed. For example, water quality can be an important matter. Experiences shows that abrasion from quarts - sand is often found in hydro turbines and can greatly reduce efficiency.
- 7.3. During the tests, it is better to check the situation of the frequency of the unit (connected to the network). In weak and unstable networks, mostly the frequency of the system is lower than the nominal value, which causes serious problems in the cooling system of the unit and finally increases the losses of the unit.
- 7.4. If both of generator and turbine efficiency tests at site are foreseen in the contract, then in order to increase the accuracy of the tests, simultaneous performing of the above mentioned tests (as far as possible) is recommended.
- 7.5. In order to measure the output power of the generator (during the tests) , mostly the existing instrument transformers in the switchboards are used. As the precision class of such instrument transformers are not suitable, using of instrument transformers with higher precision class (for example 0.2) is recommended.





Fig. 1-1 : layout of Kalan Hydro plant.

Fig. 1-2 : Arrangement of the currentmeters



Average penstock diameter = 2101.5 mm

PENSTOCK INVESTIGATION DATA SHEET TOWNSHIP OF PENSTOCK, WYOMING DESIGN: KIMBERLY INVESTIGATION, INC.				05.07.1999
POSITION	SHEET NO.	INVESTIGATION DATA II.	INVESTIGATION DATA II.	
1	6608	961	90	
2	6945	963	89	
3	6954	961	88	
4	6951	961	90	
5	6607	785	266	
6	6395	784	268	
7	6606	783	266	
8	6394	783	268	
9	6955	554	497	
10	6391	554	498	
11	6393	554	495	
12	6932	555	496	
13	6096			
				R1 = 1051
				R2 = 1052
				R3 = 1049
				R4 = 1051

Fig. 2 : Arrangement of the measuring systems





Fig. 3 : Hill diagram

EXPECTED FROM MODEL TEST +2.3% (27 MOODY)



13-07-1992

Fig. 4-1 : One unit in operation - Calculation
 of discharge measurement

POWER PLANT: KALAN				UNIT No. 1		RIVA HYDROART S.p.a.		
DISCHARGE MEASUREMENT BY CURRENT METERS				TEST No. 8		SERIAL No. 1		
CALCULATION TABLE						DATE : 12-07-92		
No.	COUNTER POSITION	COUNTS NUMBER	n [N/2T]	CALIBRATION EQUATION	VELOCITY [m/s]	RADIUS [m]	U*R [m ² /S]	R ² [m ²]
1	1A MASTER	5994	9.99	0.2441.n+0.0130	2.452	0.961	2.356	0.924
2	1B MASTER	5861	9.77	0.2409.n+0.0733	2.426	0.963	2.337	0.927
3	2A MASTER	6039	10.06	0.2409.n+0.0324	2.457	0.961	2.361	0.924
4	2B MASTER	5900	9.83	0.2436.n+0.0214	2.417	0.961	2.323	0.924
5	3A MASTER	6914	11.52	0.2343.n+0.0344	2.734	0.785	2.146	0.616
6	3B MASTER	6673	11.12	0.2393.n+0.0508	2.712	0.784	2.126	0.615
7	4A MASTER	6401	10.67	0.2475.n+0.0302	2.671	0.783	2.091	0.613
8	4B MASTER	6594	10.99	0.2433.n+0.0578	2.732	0.783	2.139	0.613
9	5A MASTER	7094	11.82	0.2388.n+0.0952	2.919	0.554	1.617	0.307
10	5B MASTER	7120	11.87	0.2369.n+0.0620	2.873	0.554	1.592	0.307
11	6A MASTER	7073	11.79	0.2403.n+0.0408	2.874	0.554	1.592	0.307
12	6B MASTER	7139	11.90	0.2382.n+0.0514	2.886	0.555	1.601	0.308
13	7A MASTER	7411	12.35	0.2478.n+0.0122	3.073	0.000	0.000	0.000
Discharge Coffin				9.298 [m3/s];	Counting Time		: 300.00 [sec];	

Fig. 4-2 : One unit in operation - Discharge measurement
by graphic integration




Fig. 4-3 : One unit in operation - Test results

RIVA HYDROART S.p.A.		21-07-92	
POWER PLANT : KALAN - UNIT N°1 -		EFFICIENCY TESTS	
Test number	8		
FINAL RESULTS			
1- WATER DENSITY AT 27.5 [°C] =	ρ_{01} =	996.449	kg/m3
2- WATER DENSITY AT 9 [°C] =	ρ_{02} =	999.798	kg/m3
3- STATIC PRESSURE UPSTREAM THE TURBINE	P1 =	43.573	bar
4- STATIC PRESSURE DOWNSTREAM THE TURBINE	P2 =	0.558	bar
5- TOTAL DISCHARGE THROUGH THE PENSTOCK	QT =	9.313	bar
6- DISCHARGE THROUGH THE UNIT UNDER TEST	Q =	9.313	bar
7- WINTER KENNEDY TAPS COEFFICIENT	KWK =	0.479	
8- TOTAL CINETIC TERM	TC =	1.038	bar
9- NET HEAD	H =	450.072	m
10- HYDRAULIC POWER	Ph =	41025.098	kW
11- MEASURED ACTIVE POWER (*)	Pa =	36890.574	kW
(*) taking into account 34.87 kW of turbine and governor losses			
12- POWER FACTOR	pf =	0.852	
13- GENERATOR LOSSES	Pb =	387.538	kW
14- MECHANICAL POWER AT TURBINE SHAFT	P =	37778.113	kW
16- HYDRAULIC TURBINE EFFICIENCY (**)	η_{ta}' =	92.616	%
(**) taking into account the obstruction effect of current meters			
17- TURBINE EFFICIENCY (***)	η_{ta} =	92.085	%
(***) caculated as stated by the contract			
18- REFERENCE NET HEAD	H' =	449.000	m
19- POWER AT REFERENCE HEAD	Pu' =	37643.180	kW
20- DISCHARGE AT REFERENCE HEAD	Q' =	9.301	m3/s

POWER PLANT : KALAN

UNIT NUMBER 1 SERIAL 1

EFFICIENCY TESTS BY CURRENT-METERS

4RS

Date: 18-07-1992

Pagina




Fig. 4-4 : One unit in operation - Efficiency versus discharge

POWER PLANT : KALAN
 UNIT NUMBER 1 SERIAL 1
 EFFICIENCY TESTS BY CURRENT-METERS

4RS

Date: 18-07-1992




Fig. 4-5 : One unit in operation - Efficiency versus power

Servizio
 Ricerca e Sviluppo

Hydroart

Eseguito

Visto

Fig. 4-6 : One unit in operation - Power versus servomotor stroke




Fig. 4-7 : One unit in operation - Discharge versus servomotor stroke




Fig. 4-8 : Two units in operation - Test results

POWER PLANT :	KALAN	UNIT	N. 1	15-07-92
TEST DATA				EFFICIENCY TESTS
Test number	13			
WATER DISCHARGE (m ³ /s)			18.4850	
WEIGHT ON PISTON MAN. (kg)			36.2100	
DOWNSTREAM FREE LEVEL (m)			1.9300	
WATER KENNEDY PRESS. (mm)			324.0000	
POWER METER Phase R (div)			37.5000	
POWER METER Phase S (div)			39.7000	
POWER METER Phase T (div)			33.5000	
AMPERE METER Phase R (div)			1.6500	
AMPERE METER Phase S (div)			1.6900	
AMPERE METER Phase T (div)			1.7000	
VOLTS METER Phase R (div)			54.2000	
SERVOMOTOR STROKE (mm)			138.0000	
WATER TEMPERATURE (°C)			8.0000	
AIR TEMPERATURE (°C)			26.5000	
OTHER UNIT RUNNING	Y=1 X=0		2.	
TEST STARTING TIME (h:m)			11.0000	

Fig. 4-9 : Two units in operation - Tests results

RIVA HYDROART S.p.A. 22-07-92
 POWER PLANT : KALAN - UNIT N° 1 - EFFICIENCY TESTS
 Test number 2
 FINAL RESULTS

1- WATER DENSITY AT 26.5 [°C] =	ρ_{01} =	996.717 kg/m ³
2- WATER DENSITY AT 8 [°C] =	ρ_{02} =	999.883 kg/m ³
3- STATIC PRESSURE UPSTREAM THE TURBINE	P ₁ =	40.382 bar
4- STATIC PRESSURE DOWNSTREAM THE TURBINE	P ₂ =	0.656 bar
5- TOTAL DISCHARGE THROUGH THE PENSTOCK	Q _T =	18.519 bar
6- DISCHARGE THROUGH THE UNIT UNDER TEST	Q =	9.312 bar
7- DISCHARGE THROUGH UNIT No. 2	Q _{WK} =	9.207 bar
8- TOTAL CINETIC TERM	TC =	1.038 bar
9- NET HEAD	H =	416.427 m
10- HYDRAULIC POWER	P _h =	37958.738 kw
11- MEASURED ACTIVE POWER (*)	P _a =	34210.707 kw
(*) taking into account 34.87 kW of turbine and governor losses		
12- POWER FACTOR	pf =	0.842
13- GENERATOR LOSSES	P _b =	865.203 kw
14- MECHANICAL POWER AT TURBINE SHAFT	P =	35075.910 kw
16- HYDRAULIC TURBINE EFFICIENCY (**)	η_{ta}' =	92.936 %
(**) taking into account the obstruction effect of current meters		
17- TURBINE EFFICIENCY (***)	η_{ta} =	92.405 %
(***) caculated as stated by the contract		
18- REFERENCE NET HEAD	H' =	404.300 m
19- POWER AT REFERENCE HEAD	Pu' =	33554.895 kw
20- DISCHARGE AT REFERENCE HEAD	Q' =	9.175 m ³ /s

Fig. 4-10: Two units in operation - Efficiency versus discharge




Fig. 4-11: Two units in operation - Efficiency versus Power





Fig. 4-12: Two units in operation - Power versus servomotor stroke






Fig. 4-13: Two units in operation - Discharge versus servomotor stroke

No. of Test	Counting time (sec)	Servomotor stroke (mm)	Flow (m ³ /s)	Net head (m)	Turbine input (kW)	Gen. Output (kW)	Gen. Losses (kW)	Turbine Efficiency (%)	Turbine Efficiency stated by (%)contract
1	300	106.5	7.629	454.393	34142.83	30229.56	824.006	91.483	90.952
2	300	119	8.534	452.640	38040.91	34068.98	860.410	92.352	91.821
3	300	135	9.565	450.070	42396.95	38088.78	903.244	92.500	91.969
4	300	96	6.913	456.293	31067.04	27163.18	798.397	90.535	90.004
5	300	85	6.084	457.230	27398.37	23207.80	764.516	88.026	87.495
6	300	76	5.425	457.897	24465.21	20205.84	744.330	86.163	85.632
7	300	64	4.515	459.876	20449.38	16159.10	729.702	83.119	82.588
8	300	129	9.255	450.072	41025.09	36890.57	887.538	92.616	92.085
9	300	140	9.816	449.136	43420.93	38926.24	915.609	92.288	91.757

Fig. 5-1 : Tests results for one unit in operation

No. of Test	Counting time (sec)	Servomotor stroke (mm)	Flow (m^3/s)	Flow through other unit (m^3/s)	Net head (m)	Turbine input (kW)	Gen. Output (kW)	Gen. Losses (kW)	Turbine Efficiency (%)	Turbine efficiency stated by (%) contract
1	300	122	8.290	9.136	420.455	34335.87	30628.97	827.51	92.145	91.614
2	300	138	9.254	9.150	416.427	37958.74	34210.71	865.20	92.936	92.405
3	300	143	9.509	9.222	414.451	38823.27	34764.72	867.91	92.313	91.782
4	300	153	10.171	8.766	413.811	41459.67	37019.41	890.28	91.969	91.438
5	300	113	7.516	9.807	421.244	31187.89	27476.41	804.35	91.210	90.679
6	300	98	6.753	9.350	426.393	28362.81	24380.24	773.32	89.216	88.685
7	300	89.5	6.103	9.294	429.830	25840.52	21365.39	752.45	86.125	85.594
8	300	68	4.921	9.063	435.546	21113.99	15769.85	723.46	78.647	78.116
9	300	135.5	9.140	8.428	420.174	37828.86	34107.64	856.82	92.959	92.428

Fig. 5-2 : Tests results for two units in operation